



Government of India
Ministry of Environment, Forest and Climate Change
(Issued by the State Environment Impact Assessment
Authority(SEIAA), Jharkhand)

To,

The Partner

JAISHREE AND KKA DEVELOPERS JV

1st Floor, Shop No.- 19 and 20, Maa Laxmi Plaza Complex, Near
 Sahjanand Chowk , Ranchi -834001

Subject: Grant of Environmental Clearance (EC) to the proposed Project Activity
 under the provision of EIA Notification 2006-regarding

Sir/Madam,

This is in reference to your application for Environmental Clearance (EC)
 in respect of project submitted to the SEIAA vide proposal number
 SIA/JH/MIS/285800/2022 dated 22 Aug 2022. The particulars of the environmental
 clearance granted to the project are as below.

1. EC Identification No.	EC22B038JH150334
2. File No.	EC/SEIAA/2022-23/2640/2022
3. Project Type	New
4. Category	B2
5. Project/Activity including Schedule No.	8(a) Building and Construction projects
6. Name of Project	Affordable Housing Project at Hazaribhag
7. Name of Company/Organization	JAISHREE AND KKA DEVELOPERS JV
8. Location of Project	Jharkhand
9. TOR Date	N/A

The project details along with terms and conditions are appended herewith from page
 no 2 onwards.

Date: 09/09/2022

(e-signed)
 Ashok Kumar, IFS
 Member Secretary
 SEIAA - (Jharkhand)

*Note: A valid environmental clearance shall be one that has EC identification
 number & E-Sign generated from PARIVESH. Please quote identification
 number in all future correspondence.*

This is a computer generated cover page.





State Level Environment Impact Assessment Authority, Jharkhand

Nursery Complex, Near Dhurwa Bus Stand, Dhurwa, Ranchi. Jharkhand-834 004

E-mail: msseiaa.jhk@gmail.com / chr-seiaajhr@gov.in

website: www.jseiaa.org

Letter No. : EC/SEIAA/2022-23/2640/2022/

Ranchi, Date :

To: Shri Vikash Ranjan,
1st Floor, Shop No. – 19 & 20,
Maa Laxmi Plaza Complex, Near Sahjanand Chowk,
District – Ranchi, State – Jharkhand,
Pin Code - 834001.

Sub. : Environmental Clearance for the project “Affordable Housing Project “Bhavya City” of M/s Jaishree and KKA Developers JV at Village : Hurhuru, Tehsil : Bishungarh, Thana no. : 147, Distt. : Hazaribagh, Jharkhand” (Proposal No. : SIA/JH/MIS/285800/2022) – regarding.

Ref. : Your application no. - Nil, dated - 14.08.2022.

It is in reference to the project “Affordable Housing Project “Bhavya City” of M/s Jaishree and KKA Developers JV at Village : Hurhuru, Tehsil : Bishungarh, Thana no. : 147, Distt. : Hazaribagh, Jharkhand” submitted by you for seeking prior Environmental Clearances (EC).

This is a new project which has been taken for appraisal on 16.08.2022.

Project Category: 8(a) Category B2 – Application for Environment Clearance

Project is classified as Category 8(a) as per EIA Notification as the built up area is less than 1,50,000 sq m and development area is less than 50 ha.

Jaishree and KKA Developer J.V. are proposed to develop residential Building “Bhavya City” Project on the total land area measuring 4503.76 sqm. The proposed build up area is 23443.77 sqm. Affordable Housing “Bhavya City” at Thana No. 147, Village : Hurhuru, Tehsil : Bishungarh, Distt. : Ranchi, Jharkhand.

Salient Features of the Project:

Sr. No.	Particulars	
1.	Latitude	23°58'31.64"N
2.	Longitude	85°22'22.36"E

3.	Plot Area	4503.76 Sqm
4.	Proposed Ground Coverage	1520.37 Sqm
5.	Proposed FAR @3.48	15693.43 Sqm.
6.	Parking Area	5155.34 Sqm.
7.	Others (Non FAR)	2595 Sqm.
8.	Total Built-up Area	23443.77 Sqm.
9.	Total Parking Required (ECS)	116 Nos.
10.	Total Parking Proposed (ECS)	Four-wheeler: 163 Nos. Two wheeler: 177 Nos.
11.	Total Green Area provided @15.05%	677.73 Sqm.
12.	Rain Water Harvesting Pits (with size)	3 Nos.
13.	STP Capacity	100 KLD
14.	Maximum Height of the Building (m)	34.3 m
15.	Power Requirement	~1000 KW
16.	Power Backup	2 DGs of 250 KVA each
17.	Total Water Requirement	~93 KLD
18.	Fresh/Domestic Water Requirement	~60 KLD
19.	Reuse of Recycled Water	~34 KLD
20.	Waste Water Generated	~77 KLD
21.	Solid Waste Generated (Operational)	~392 Kg/day
22.	Biodegradable Waste (Operational)	~235 Kg/day
23.	Non-Biodegradable Waste (Operational)	~157 Kg/day
24.	Number of Tower	03
25.	Basement	01
26.	Stories	B+G+11
27.	R+U Value of Material used (Glass)	U-value-5.6 w/m ² R-value- 0.17 w/m ²
28.	Total Cost of the project:	i) Land Cost 656.13 Lakh
		ii) Construction Cost 378.38 Lakh
		Total 4439.95 Lakh
29.	EMP Budget	During Construction: Capital: 25 Lakhs Recurring: 13.5 Lakhs Operational Cost: Capital: 81 Lakhs Recurring: 19.5 Lakhs
30.	Incremental Load in respect of:	i) PM ₁₀ (24 hr) 1.64
		ii) NO ₂ (24 hr) 15.2
		iii) CO (24 hr) 116.4

31.	Construction Phase:	i) Power Back-up	2 DG of 250 KVA each
		ii) Water Requirement & Source	Fresh water – 9 KLD Treated wastewater-12 KLD Source: Tanker water supply
		iii) STP (Modular)	20 KLD

Khata no. & Plot no. of the project:

Khata No	Plot no
1	1053
	1054
	1055
15	1059
	1060
32	1056

Floor wise Built-up Area Details:

S. No.	Description	Block A (Sqm.)	Block B (Sqm.)	Block C (Sqm.)
1	Basement Floor	2728.35	1416.08	360.32
2	Ground Floor	474.54	742.10	387.36
3	First Floor	524.35	744.05	387.36
4	Second Floor	527.42	772.86	387.36
5	Third Floor	527.42	772.86	387.36
6	Fourth Floor	527.42	772.86	387.36
7	Fifth Floor	527.42	772.86	387.36
8	Sixth Floor	527.42	772.86	387.36
9	Seventh Floor	527.42	772.86	387.36
10	Eight Floor	527.42	772.86	352.32
11	Nineth Floor	527.42	772.86	--
12	Tenth Floor	527.42	772.86	--
13	Eleventh Floor	527.42	772.86	--
		9001.39	10630.86	3811.52

Details of Building Blocks:

Building Block	No. of Floors	No. of Flats
Block A	B+G+11	44
Block B	B+G+11	73
Block C	B+G+8	63
Total		180

SA

GS

A

Calculation of Population:

Details	Dwelling unit	Person per Dwelling unit	Population
Block A	44	5	220
Block B	73	5	365
Block C	63	4	252
Visitors @15% of total Population			126
Total			963

Parking requirement:

Total Parking Required (ECS)	116 Nos.
Total Parking Proposed (ECS)	Four-wheeler: 163 Nos. Two wheeler: 177 Nos.

Site Surroundings and Connectivity Details:

S. No.	Connectivity & Site Surroundings		
	Description		Distance and Direction
1.	Nearest Railway Station	Hazaribagh Town Railway Station	Approx. 3.38 Km towards WNW
2.	Nearest Airport	Birsa Munda Airport, Ranchi	Approx. 73.03 Km South
3.	Nearest Village	Patratu Hurhuru Subash Nagar	0.29 Km towards ESE 0.93 Km towards WNW 0.97 Km towards WNW
4.	Nearest Highway/Roads	NH-20 Patratu Rd. Hurhuru Rd. Hazaribagh Brakagaon Rd.	Approx. 0.03 Km towards East Approx. 0.17 Km towards SSE Approx. 0.51 Km towards North Approx. 1.48 Km towards West
5.	Nearest School & College	Hurhuru Sarkari School Government Middle School, Bharouna Markham College of Commerce St. Kiran Girl's High School	Approx. 0.49 Km towards NW Approx. 1.12 Km towards NE Approx. 1.47 Km towards West Approx. 0.26 Km towards NE

GA

B
4

h

6.	Nearest Hospital	Kshitij Hospital & Research Centre Sadar Hospital, Hazaribagh St. Columba's (Mission) Hospital, Hazaribagh	Approx. 0.78 Km towards SSE Approx. 2.96 Km towards NW Approx. 1.63 Km towards NW
7.	Places of worship	Shiv Temple, Hurhuru Shiv Mandir, Patratu Pandiji Hurhuru Temple	Approx. 0.27 Km towards NW Approx. 0.19 Km towards East Approx. 0.25 Km towards North

Statutory Clearances:

1	DFO Forest Distance	:	DFO, Hazaribagh East Division vide letter no. 2116, dated 04.08.2022 certified that the distance of reserved / protected forest is more than 250 m from proposed project site.
2	DFO Wild Life	:	DFO, Wildlife Hazaribagh vide letter no. 790, dated 20.04.2022 certified that the National Park & Sanctuary is not within 10 km from project site and proposed project is not situated in any ESZ.
3	CO certificate	:	The CO, Hazaribagh (Sadar) vide letter no. 938, dated 08.07.2022 has certified that applied plot no. belongs to Raiyati land as per Khatiyani. None of the plots are mentioned as "Jungle Jhari". PAs has also submitted the affidavit affirming that the proposed project area does not falls under "Jangle Jhari".
4	Fire Department	:	A Fire Advisory has been issued by Fire Department, Jharkhand, Ranchi, vide letter no. 1864/Tech./2021, dated 02.07.2021.
5	Building Plan	:	Conceptual Plan submitted.
6.	AAI	:	Project Authority has submitted the affidavit affirming that there is no Airport available in Hazaribagh district. In future if it is required a permission should be obtained from Airport Authority of India.

Water & Waste water requirement Details

Sl. No.	No /name of block	No of dwelling unit	Person per D.U.	Population	LPCD*	Domestic water requirement	Flushing water	Total water requirement	Waste water generation @80%
1	A	44	5	220	100	14740	7260	22000	19052
2	B	73	5	365	100	24455	12045	36500	31609
3	C	63	4	252	100	16884	8316	25200	21823.2
4	Visitor @15% of total population			126	45	3767	1883	5650	4896.45
	Total	180		963		59846	29504	89350	77381

24

5

1

	KLD					59.85	29.50	89.35	77.38
	Waste water generation			77.38					
	STP input			77.38					
	STP size @20% higher than wastewater			92.86					
	STP treated water			61.90					
Reuse of treated water									
1	Flushing		29.50						
2	Horticulture +DG		4.38						

Category	Total Quantity (KLD)
Fresh water Req. for domestic purpose	~60
Flushing water Req.	~30
Sewage generation (@80% of the fresh water consumption + 100% flushing water & swimming Pool)	~77 (47+30)
Capacity of STP	~93
Recovered water from STP (80% of Waste water)	~70
1. Flushing	~30
2. Landscaping	~4
3. Discharge to Sewer	~36

Solid Waste Requirement

S.No.	Category of Solid Waste	Waste Generation Rate	Formula	Total Population	Waste Generated	Bio-degradable	Non-biodegradable
1	Residential Refuse	0.3 to 0.6 kg/cap/day	Total Population*0.45	837	376.65	226	151
2	Visitors	0.05 to 0.2 kg/cap/day	Total Population*0.125	126	15.75	9.45	6.3
	Total			963	392	235	157

ENVIRONMENT MANAGEMENT

Green Belt Development

- Combination of local trees and shrubs are planned within the project site.
- Green area will be provided in 677.73 sqm. (@15.05% of plot area), which will enhance the beauty of the site and help to combat air and noise pollution. (Plan Attached)

- The plant species will be selected on the basis of Guidelines for Developing Green Belts, CPCB March 2000.

Solid Waste Management

During Construction Phase

- Construction yards are proposed for storage of construction material.
- Excavated top soil will be stored in temporary constructed soil bank and will be reused for landscaping of the project.
- Remaining soil will be utilized for refilling/road work/raising of site level at locations.
- There will be "Refuse Containers" at site for the management of domestic waste generated by the construction labourers and these containers will be emptied at least once daily.
- Cement bags, waste paper and packing material (cardboard) will be sold off to recyclers.

During Operation Phase

- The solid waste will be segregated at source & collected.
- Adequate number of colored bins (green, white & Black) separate for bio-degradable, non-biodegradable and Hazardous waste are proposed to be provided at the strategic location within site.
- Bio-degradable (will be composted through organic waste converter).
- Recyclable wastes will be disposed to govt. or SPCB approved third party vendors.
- Dewatered sludge can be buried underground in a sanitary landfill. It also may be spread on agricultural land in order to make use of its value as a soil conditioner and fertilizer.
- The Hazardous waste generated will be managed as per the Hazardous and Other Wastes (Management and Trans boundary Movement) Rules, 2016.
- Horticultural Waste is composted and used for gardening purposes.

Water Quality Management

During Construction Phase

- The site drainage will be planned in such a way that there is no accumulation of water/wastewater within the project premises or in the vicinity of the site.
- Mobile toilets to be provided for construction Laborers.
- Generated waste water will be collected through tankers and dispose to septic tank for treatment.

During Operation Phase

- STP of capacity i.e. 94 KLD is proposed for treatment of wastewater.
- Treated waste water would be reused for Horticulture, DG cooling, flushing and in nearby construction site/sewer.
- Use of water efficient plumbing fixtures to conserve water.
- Approx. 60 KLD of fresh water is required during operational phase of the project.

Air Quality Management

- Warehouse/stock yard will be provided for storage of construction material





- Covering of stored construction materials with tarpaulin covers which will be resold to authorized construction material handling agency for reuse.
- Covering of trucks carrying construction materials.
- Dust suppression by water sprinkling.
- Adequate maintenance of construction equipment & vehicles.
- Wheel wash facility at the entry/exit of the site to prevent dust emissions.
- Periodical Ambient Air Quality Monitoring.
- PUC Certified vehicles.
- Glow signs Speed Limits to 20 kmph to reduce emissions on site will be displayed at the important junctions.

Energy conservation

- Solar Panels will be used in Street Lights, Common area, Pumping area.

State Level Environment Level Impact Assessment Authority (SEIAA), Jharkhand in its 97th meeting held on 25th & 26th August, 2022 discussed the project proposal along with recommendations made by SEAC in its 96th meeting held on 16th, 17th, 18th and 19th August, 2022 and decided to grant EC to the project.

On the basis of recommendation of SEAC and decision of SEIAA to grant of EC, Environmental Clearance is hereby issued to the **“Affordable Housing Project “Bhavya City” of M/s Jaishree and KKA Developers JV at Village : Hurhuru, Tehsil : Bishungarh, Thana no. : 147, Distt. : Hazaribagh, Jharkhand”** alongwith the following specific conditions as recommended by SEAC:

I. Specific Conditions:

- i. This Environmental Clearance is valid subject to the following condition below –
That this project has-
 - a. Obtained all legal rights to operate at concerned place.
 - b. Complied with all existing concerned laws of the land and
 - c. Complied with the decisions of SEIAA on the issue of Environmental Clearance till date.
- ii. Environment management system including organization structure to be drawn to ensure compliance of EC conditions stipulated based on principles of Continuous Improvement and periodical management review.
- iii. All raw material to be stored only under covered shed.
- iv. PAs to offset (upto20%) consumption of conventional energy sources by promoting use of solar energy, passive energy utilization, optimum fenestration, shading effect and heat islands.





- v. Developers to promote energy conservation measures such that it offsets not less than 02 % of connected load. It is to be achieved by solar panels etc meeting ECBC norms.
- vi. Trees should be developed & maintained not less than 15% of project area.
- vii. Organic Waste Converter (OWC) to be installed of sufficient capacity such that all organic waste (bio degradable) generated is used as compost manure.
- viii. Developers/Company to install STP of sufficient capacity such that all the sewer produced is treated and reused.
- ix. Developers/Company to install Rain water harvesting structures such that all the roof top water runoff is collected and harvested including reuse on 100% basis.
- x. Developers/Company to conduct and submit carbon footprint and carbon sequestration study report including mitigation measures as a part of EC compliance.
- xi. Water runoff originating from open non constructed areas of project premises to be harvested /guided in such a way that it does not create water logging condition outside.
- xii. Sufficient number of EV fast charging point to be installed.
- xiii. Ground water will not be used without the permission of competent Authority.
- xiv. After approval of Building Plan from competent Authority, it should be submitted to the SEIAA.
- xv. This Environmental Clearance is granted subject to final outcome of Hon'ble Supreme Court of India, Hon'ble High Court, Hon'ble NGT, MoEF & CC and any other Court of Law, if any, as may be applicable to this project.
- xvi. Environmental clearance is subject to obtaining prior clearance from forestry and Wildlife angle including clearance from standing committee of NBWL, as may be applicable to this project (in case any fauna occurs / is found in the Project area or if the area involves forest land or Wildlife habitat i.e. core zone of elephant/tiger reserve etc. and or located with in 10 km. of protected area).
- xvii. The project proponent may apply simultaneously for forest and NBWL clearance, in order to complete the formalities without undue delay, which till process on their respective merits, no rights will vest in or accrue to them unless all clearance are obtained.
- xviii. This Environmental Clearance shall be valid subject to the sustainable environmental management.

II. Statutory Compliance :

- i. The project proponent shall obtain all necessary clearance/ permission from all relevant agencies including town planning authority before commencement of work. All the construction shall be done in accordance with the local building byelaws.







- ii. The approval of the Competent Authority shall be obtained for structural safety of buildings due to earthquakes, adequacy of fire fighting equipment etc as per National Building Code including protection measures from lightening etc.
- iii. The project proponent shall obtain forest clearance under the provisions of Forest (Conservation) Act, 1986, in case of the diversion of forest land for non-forest purpose involved in the project.
- iv. In the writ petition (Civil) no. 202/1995, T.N. Godaverman Thirumulpad vs union of India and ors. the Hon'ble Supreme Court passed an order dated 03.06.2022 " National Park or Wildlife Sanctuary must have an ESZ of minimum 01 km in which the activities prescribed and prescribed in the guidelines of 09th February, 2011 shall be strictly adhered to".
- v. The project proponent shall obtain clearance from the National Board for Wildlife, if applicable.
- vi. The project proponent shall obtain Consent to Establish / Operate under the provisions of Air (Prevention & Control of Pollution) Act, 1981 and the Water (Prevention & Control of Pollution) Act, 1974 from the concerned State Pollution Control Board/ Committee.
- vii. The project proponent shall obtain the necessary permission for drawl of ground water / surface water required for the project from the competent authority.
- viii. A certificate of adequacy of available power from the agency supplying power to the project along with the load allowed for the project should be obtained.
- ix. All other statutory clearances such as the approvals for storage of diesel from Chief Controller of Explosives, Fire Department, Civil Aviation Department shall be obtained, as applicable, by project proponents from the respective competent authorities.
- x. The provisions of the Solid Waste (Management) Rules, 2016, e-Waste (Management) Rules, 2016, and the Plastics Waste (Management) Rules, 2016 shall be followed.
- xi. The project proponent shall follow the ECBC/ECBC-R prescribed by Bureau of Energy Efficiency, Ministry of Power strictly.
- xii. Provision shall be made for the housing of construction labour within the site with all necessary infrastructure and facilities such as fuel (kerosene/gas) for cooking, safe drinking water, medical health care, etc. The housing may be in the form of temporary structures to be removed after completion of the project.
- xiii. Provision of drinking water, waste water disposal, solid wastes management and primary health facilities shall be ensured for labour force. Proper sanitation facilities shall be provided at the construction site to prevent health related problems. Domestic as well as sanitary wastes from construction camps shall be cleared regularly.
- xiv. All the labourers to be engaged for construction works shall be screened for health and adequately treated before issue of work permits. The contractor shall ensure periodic health check-up of construction workers.



- xv. All vehicles/equipment deployed during construction phase shall be ensured in good working condition and shall conform to applicable air and noise emission standards. These shall be operated only during non-peaking hours.
- xvi. Accumulation/stagnation of water shall be avoided ensuring vector control.
- xvii. Water during construction phase should be preferred from Municipal supply.
- xviii. Unskilled construction labourers shall be recruited from the local areas.
- xix. Monitoring of ground water table and quality once in three months shall be carried out. Construction of tube wells, bore wells shall be strictly regulated.
- xx. Adequate provision shall be made to cater the parking needs. Parking spaces standards as given in "Manual on Norms and Standards for Environmental Clearance of Large Construction Projects" issued by Ministry of Environment and Forests, Government of India shall be adopted.
- xxi. Rest room facilities shall be provided for service population.
- xxii. Water body falling within premises (if any) shall not be lined or no embankment shall be cemented. The water bodies, if any, shall be kept in natural conditions without disturbing the ecological habitat.
- xxiii. Construction shall conform to the requirements of local seismic regulations. The project proponent shall obtain permission for the plans and designs including structural design, standards and specifications of all construction work from concerned authority.

III. Air quality monitoring and preservation:

- i. Notification GSR 94(E) dated 25.01.2018 of MoEF&CC regarding Mandatory Implementation of Dust Mitigation Measures for Construction and Demolition Activities for projects requiring Environmental Clearance shall be complied with.
- ii. A management plan shall be drawn up and implemented to contain the current exceedance in ambient air quality at the site.
- iii. The project proponent shall install system to carryout Ambient Air Quality monitoring for common/criterion parameters relevant to the main pollutants released (e.g. PM10 and PM25) covering upwind and downwind directions during the construction period.
- iv. Diesel power generating sets proposed as source of backup power should be of enclosed type and conform to rules made under the Environment (Protection) Act, 1986. The height of stack of DG sets should be equal to the height needed for the combined capacity of all proposed DG sets. Use of low sulphur diesel. The location of the DG sets may be decided with in consultation with State Pollution Control Board.
- v. Construction site shall be adequately barricaded before the construction begins. Dust, smoke & other air pollution prevention measures shall be provided for the building as well as the site. These measures shall include screens for the building under construction,



continuous dust/ wind breaking walls all around the site (at least 3 meter height). Plastic/tarpaulin sheet covers shall be provided for vehicles bringing in sand, cement, murram and other construction materials prone to causing dust pollution at the site as well as taking out debris from the site.

- vi. Sand, murram, loose soil, cement, stored on site shall be covered adequately so as to prevent dust pollution.
- vii. Wet jet shall be provided for grinding and stone cutting.
- viii. Unpaved surfaces and loose soil shall be adequately sprinkled with water to suppress dust.
- ix. All construction and demolition debris shall be stored at the site (and not dumped on the roads or open spaces outside) before they are properly disposed. All demolition and construction waste shall be managed as per the provisions of the Construction and Demolition Waste Rules 2016.
- x. The diesel generator sets to be used during construction phase shall be low sulphur diesel type and shall conform to Environmental (Protection) prescribed for air and noise emission standards.
- xi. The gaseous emissions from DG set shall be dispersed through adequate stack height as per CPCB standards. Acoustic enclosure shall be provided to the DG sets to mitigate the noise pollution. Low sulphur diesel shall be used. The location of the DG set and exhaust pipe height shall be as per the provisions of the Central Pollution Control Board (CPCB) norms.
- xii. For indoor air quality the ventilation provisions as per National Building Code of India.

IV. Water quality monitoring and preservation:

- i. The natural drain system should be maintained for ensuring unrestricted flow of water. No construction shall be allowed to obstruct the natural drainage through the site, on wetland and water bodies. Check dams, bio-swales, landscape, and other sustainable urban drainage systems (SUDS) are allowed for maintaining the drainage pattern and to harvest rain water.
- ii. Buildings shall be designed to follow the natural topography as much as possible. Minimum cutting and filling should be done.
- iii. Total fresh water use shall not exceed the proposed requirement as provided in the project details.
- iv. The quantity of fresh water usage, water recycling and rainwater harvesting shall be measured and recorded to monitor the water balance as projected by the project proponent. The record shall be submitted to the Regional Office, MoEF&CC along with six monthly Monitoring reports.



- v. A certificate shall be obtained from the local body supplying water, specifying the total annual water availability with the local authority, the quantity of water already committed, the quantity of water allotted to the project under consideration and the balance water available. This should be specified separately for ground water and surface water sources, ensuring that there is no impact on other users.
- vi. At least 20% of the open spaces as required by the local building bye-laws shall be pervious. Use of Grass pavers, paver blocks with at least 50% opening, landscape etc. would be considered as pervious surface.
- vii. Installation of dual pipe plumbing for supplying fresh water for drinking, cooking and bathing etc and other for supply of recycled water for flushing, landscape irrigation, car washing, thermal cooling, conditioning etc. shall be done.
- viii. Use of water saving devices/ fixtures (viz. low flow flushing systems; use of low flow faucets tap aerators etc) for water conservation shall be incorporated in the building plan.
- ix. Separation of grey and black water should be done by the use of dual plumbing system. In case of single stack system separate recirculation lines for flushing by giving dual plumbing system be done.
- x. Water demand during construction should be reduced by use of pre-mixed concrete, curing agents and other best practices referred.
- xi. The local bye-law provisions on rain water harvesting should be followed. If local byelaw provision is not available, adequate provision for storage and recharge should be followed as per the Ministry of Urban Development Model Building Byelaws, 2016. Rain water harvesting recharge pits/storage tanks shall be provided for ground water recharging as per the CGWB norms.
- xii. A rain water harvesting plan needs to be designed where the recharge bores of minimum one recharge bore per 5,000 square meters of built up area and storage capacity of minimum one day of total fresh water requirement shall be provided. In areas where ground water recharge is not feasible, the rain water should be harvested and stored for reuse. The ground water shall not be withdrawn without approval from the Competent Authority.
- xiii. All recharge should be limited to shallow aquifer.
- xiv. No ground water shall be used during construction phase of the project.
- xv. Any ground water dewatering should be properly managed and shall conform to the approvals and the guidelines of the CGWA in the matter. Formal approval shall be taken from the CGWA for any ground water abstraction or dewatering.
- xvi. The quantity of fresh water usage, water recycling and rainwater harvesting shall be measured and recorded to monitor the water balance as projected by the project proponent. The record shall be submitted to the Regional Office, MoEF&CC along with six monthly Monitoring reports.



- xvii. Sewage shall be treated in the STP with tertiary treatment. The treated effluent from STP shall be recycled/re-used for flushing, AC make up water and gardening. As proposed, no treated water shall be disposed in to municipal drain.
- xviii. No sewage or untreated effluent water would be discharged through storm water drains.
- xix. Onsite sewage treatment of capacity of treating 100% waste water to be installed based on the MBBR/MBR/SBR technology. The installation of the Sewage Treatment Plant (STP) shall be certified by an independent expert and a report in this regard shall be submitted to the Ministry before the project is commissioned for operation. Treated waste water shall be reused on site for landscape, flushing, cooling tower, and other end-uses. Excess treated water shall be discharged as per statutory norms notified by Ministry of Environment, Forest and Climate Change. Natural treatment systems shall be promoted.
- xx. Periodical monitoring of water quality of treated sewage shall be conducted. Necessary measures should be made to mitigate the odour problem from STP.
- xxi. Sludge from the onsite sewage treatment, including septic tanks, shall be collected, conveyed and disposed as per the Ministry of Urban Development, Central Public Health and Environmental Engineering Organization (CPHEEO) Manual on Sewerage and Sewage Treatment Systems, 2013.

V. Noise monitoring and prevention:

- i. Ambient noise levels shall conform to residential area/commercial area/industrial area/silence zone both during day and night as per Noise Pollution (Control and Regulation) Rules, 2000. Incremental pollution loads on the ambient air and noise quality shall be closely monitored during construction phase. Adequate measures shall be made to reduce ambient air and noise level during construction phase, so as to conform to the stipulated standards by CPCB / SPCB.
- ii. Noise level survey shall be carried as per the prescribed guidelines and report in this regard shall be submitted to Regional Officer of the Ministry as a part of six-monthly compliance report.
- iii. Acoustic enclosures for DG sets, noise barriers for ground-run bays, ear plugs for operating personnel shall be implemented as mitigation measures for noise impact due to ground sources.

VI. Energy Conservation measures:

- i. Compliance with the Energy Conservation Building Code (ECBC) of Bureau of Energy Efficiency shall be ensured. Buildings in the States which have notified their own ECBC, shall comply with the State ECBC.
- ii. Outdoor and common area lighting shall be LED.
- iii. Concept of passive solar design that minimize energy consumption in buildings by using design elements, such as building orientation, landscaping, efficient building envelope,

04

By


1

appropriate fenestration, increased day lighting design and thermal mass etc. shall be incorporated in the building design. Wall, window, and roof u-values shall be as per ECBC specifications.

- iv. Energy conservation measures like installation of CFLs/ LED for the lighting the area outside the building should be integral part of the project design and should be in place before project commissioning.
- v. Solar, wind or other Renewable Energy shall be installed to meet electricity generation equivalent to 1% of the demand load or as per the state level/ local building bye-laws requirement, whichever is higher.
- vi. Solar power shall be used for lighting in the apartment to reduce the power load on grid. Separate electric meter shall be installed for solar power. Solar water heating shall be provided to meet 20% of the hot water demand of the commercial and institutional building or as per the requirement of the local building bye-laws, whichever is higher. Residential buildings are also recommended to meet its hot water demand from solar water heaters, as far as possible.

VII. Waste Management:

- i. A certificate from the competent authority handling municipal solid wastes, indicating the existing civic capacities of handling and their adequacy to cater to the M.S.W. generated from project shall be obtained.
- ii. Disposal of muck during construction phase shall not create any adverse effect on the neighboring communities and be disposed taking the necessary precautions for general safety and health aspects of people, only in approved sites with the approval of competent authority.
- iii. Separate wet and dry bins must be provided in each unit and at the ground level for facilitating segregation of waste. Solid waste shall be segregated into wet garbage and inert materials.
- iv. Organic waste compost/ Vermiculture pit/ Organic Waste Converter within the premises with a minimum capacity of 0.3 kg /person/day must be installed.
- v. All non-biodegradable waste shall be handed over to authorized recyclers for which a written tie up must be done with the authorized recyclers.
- vi. Any hazardous waste generated during construction phase, shall be disposed off as per applicable rules and norms with necessary approvals of the State Pollution Control Board.
- vii. Use of environment friendly materials in bricks, blocks and other construction materials, shall be required for at least 20% of the construction material quantity. These include Fly Ash bricks, hollow bricks, AACs, Fly Ash Lime Gypsum blocks, Compressed earth blocks, and other environment friendly materials.



- viii. Fly ash should be used as building material in the construction as per the provision of Fly Ash Notification of September, 1999 and amended as on 27th August, 2003 and 25th January, 2016. Ready mixed concrete must be used in building construction.
- ix. Any wastes from construction and demolition activities related thereto shall be managed so as to strictly conform to the Construction and Demolition Rules, 2016.
- x. Used CFLs and TFLs should be properly collected and disposed off/sent for recycling as per the prevailing guidelines/ rules of the regulatory authority to avoid mercury contamination.

VIII. Green Cover:

- i. No tree can be felled/transplant unless exigencies demand. Where absolutely necessary, tree felling shall be with prior permission from the concerned regulatory authority. Old trees should be retained based on girth and age regulations as may be prescribed by the Forest Department. Plantations to be ensured species (cut) to species (planted).
- ii. A minimum of 1 tree for every 80 sqm of land should be planted and maintained. The existing trees will be counted for this purpose. The landscape planning should include plantation of native species. The species with heavy foliage, broad leaves and wide canopy cover are desirable. Water intensive and/or invasive species should not be used for landscaping.
- iii. Where the trees need to be cut with prior permission from the concerned local Authority, compensatory plantation in the ratio of 1:10 (i.e. planting of 10 trees for every 1 tree that is cut) shall be done and maintained. Plantations to be ensured species (cut) to species (planted). Area for green belt development shall be provided as per the details provided in the project document.
- iv. Topsoil should be stripped to a depth of 20 cm from the areas proposed for buildings, roads, paved areas, and external services. It should be stockpiled appropriately in designated areas and reapplied during plantation of the proposed vegetation on site.

IX. Transport:

- i. A comprehensive mobility plan, as per MoUD best practices guidelines (URDPFI), shall be prepared to include motorized, non-motorized, public, and private networks. Road should be designed with due consideration for environment, and safety of users. The road system can be designed with these basic criteria.
 - a. Hierarchy of roads with proper segregation of vehicular and pedestrian traffic.
 - b. Traffic calming measures.
 - c. Proper design of entry and exit points.
 - d. Parking norms as per local regulation.



- ii. Vehicles hired for bringing construction material to the site should be in good condition and should have a pollution check certificate and should conform to applicable air and noise emission standards be operated only during non-peak hours.
- iii. A detailed traffic management and traffic decongestion plan shall be drawn up to ensure that the current level of service of the roads within a 05 kms radius of the project is maintained and improved upon after the implementation of the project. This plan should be based on cumulative impact of all development and increased habitation being carried out or proposed to be carried out by the project or other agencies in this 05 Kms radius of the site in different scenarios of space and time and the traffic management plan shall be duly validated and certified by the State Urban Development department and the P.W.D./ competent authority for road augmentation and shall also have their consent to the implementation of components of the plan which involve the participation of these departments.

X. Human Health Issue:

- i. All workers working at the construction site and involved in loading, unloading, carriage of construction material and construction debris or working in any area with dust pollution shall be provided with dust mask.
- ii. For indoor air quality the ventilation provisions as per National Building Code of India.
- iii. Emergency preparedness plan based on the Hazard identification and Risk Assessment (HIRA) and Disaster Management Plan shall be implemented.
- iv. Provision shall be made for the housing of construction labour within the site with all necessary infrastructure and facilities such as fuel for cooking, mobile toilets, mobile STP, safe drinking water, medical health care, crèche etc. The housing may be in the form of temporary structures to be removed after the completion of the project.
- v. Occupational health surveillance of the workers shall be done on a regular basis.
- vi. A First Aid Room shall be provided in the project both during construction and operations of the project.

XI. Corporate Environment Responsibility:

- i. The project proponent shall comply with the provisions contained in this Ministry's OM vide F.No. 22-65/2017-IA.III dated 1st May 2018, as applicable, regarding Corporate Environment Responsibility.
- ii. The company shall have a well laid down environmental policy duly approved by the Board of Directors. The environmental policy should prescribe for standard operating procedures to have proper checks and balances and to bring into focus any infringements/deviation/violation of the environmental / forest / wildlife norms / conditions. The company shall have defined system of reporting infringements / deviation / violation of the environmental / forest / wildlife norms / conditions and / or shareholders



/ stake holders. The copy of the board resolution in this regard shall be submitted to the MoEF&CC as a part of six-monthly report.

- iii. A separate Environmental Cell both at the project and company head quarter level, with qualified personnel shall be set up under the control of senior Executive, who will directly to the head of the organization.
- iv. Action plan for implementing EMP and environmental conditions along with responsibility matrix of the company shall be prepared and shall be duly approved by competent authority. The year wise funds earmarked for environmental protection measures shall be kept in separate account and not to be diverted for any other purpose. Year wise progress of implementation of action plan shall be reported to the Ministry/Regional Office along with the Six Monthly Compliance Report.

XII. Miscellaneous:

- i. The project proponent shall prominently advertise it at least in two local newspapers of the District or State, of which one shall be in the vernacular language within seven days indicating that the project has been accorded environment clearance and the details of MoEF&CC/SEIAA website where it is displayed.
- ii. The copies of the environmental clearance shall be submitted by the project proponents to the Heads of local bodies, Panchayats and Municipal Bodies in addition to the relevant offices of the Government who in turn has to display the same for 30 days from the date of receipt.
- iii. The project proponent shall upload the status of compliance of the stipulated environment clearance conditions, including results of monitored data on their website and update the same on half-yearly basis.
- iv. The project proponent shall submit six-monthly reports on the status of the compliance of the stipulated environmental conditions on the website of the ministry of Environment, Forest and Climate Change at environment clearance portal.
- v. The project proponent shall submit the environmental statement for each financial year in Form-V to the concerned State Pollution Control Board as prescribed under the Environment (Protection) Rules, 1986, as amended subsequently and put on the website of the company.
- vi. The project proponent shall inform the Regional Office as well as the Ministry, the date of financial closure and final approval of the project by the concerned authorities, commencing the land development work and start of production operation by the project.
- vii. The project authorities must strictly adhere to the stipulations made by the State Pollution Control Board and the State Government.

At

St

h

- viii. The project proponent shall abide by all the commitments and recommendations made in the EIA/EMP report, commitment made during Public Hearing and also that during their presentation to the Expert Appraisal Committee.
- ix. No further expansion or modifications in the plant shall be carried out without prior approval of the Ministry of Environment, Forests and Climate Change (MoEF&CC).
- x. Concealing factual data or submission of false/fabricated data may result in revocation of this environmental clearance and attract action under the provisions of Environment (Protection) Act, 1986.
- xi. The Ministry / SEIAA / SEAC may revoke or suspend the clearance, if implementation of any of the above conditions is not satisfactory.
- xii. The Ministry / SEIAA / SEAC reserves the right to stipulate additional conditions if found necessary. The Company in a time bound manner shall implement these conditions.
- xiii. It shall be mandatory for the project management to submit six (06) monthly compliance report in respect of the stipulated prior environmental clearance terms and conditions in hard copies and soft copies to the regulatory authority concerned Regional Office of MoEF & CC at Ranchi and Jharkhand State Pollution Control Board (J.S.P.C.B.), Ranchi / CPCB / SEIAA.
- xiv. The above conditions shall be enforced, inter-alia under the provisions of the Water (Prevention & Control of Pollution) Act, 1974, the Air (Prevention & Control of Pollution) Act, 1981, the Environment (Protection) Act, 1986, Hazardous and Other Wastes (Management and Transboundary Movement) Rules, 2016 and the Public Liability Insurance Act, 1991 along with their amendments and Rules and any other orders passed by the Hon'ble Supreme Court of India / High Courts and any other Court of Law relating to the subject matter.
- xv. The SEIAA, Jharkhand or any other competent Authority may alter modify the above conditions or stipulate any further condition in the interest of Environment Protection.
- xvi. Any appeal against this EC shall lie with the National Green Tribunal, if preferred, within a period of 30 days as prescribed under Section 16 of the National Green Tribunal Act, 2010.

Sd/-

Member Secretary
State Level Environment Impact
Assessment Authority, Jharkhand.

Memo No. : EC/SEIAA/2022-23/2640/2022/ 237

Ranchi, Date : 02/09/2022

Copy to:


- I. Additional Chief Secretary, Department of Forests, Environment & Climate Change,
Govt. of Jharkhand.







2. Deputy Commissioner, District- Hazaribagh, Jharkhand.
3. Divisional Forest Officer, Hazaribagh East Forest Division, Hazaribagh, Jharkhand.
4. Divisional Forest Officer, Wildlife Division, Hazaribagh, Jharkhand.
5. Director IA Division, Monitoring Cell, MoEF and Climate Change, Indira Paryavaran Bhavan, Jorbag Road, Aliganj, New Delhi – 110003.
6. Ministry of Environment, Forest and Climate Change, 2nd Floor, Jharkhand State Housing Board (HQ), Harmu Chowk, Ranchi, Jharkhand – 834002.
7. Member Secretary, Jharkhand State Pollution Control Board, Ranchi.
8. Secretary, Jharkhand State Expert Appraisal Committee, Ranchi.
9. Website.
10. Guard file.


Member Secretary
State Level Environment Impact
Assessment Authority, Jharkhand

